MYSORE DIVISION.

Dated 2nd July 1931.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 27th July 1931, for Repairing the sluice and channels of Thonnur Tank, Seringapatam Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1932.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore, between the hours of 11 A.M. to 5 P.M., on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 (one hundred and fifty only) in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for repairing the sluice and channels of Thonnur tank, Seringapatam Taluk", in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tendered rates will not be increased on any account.

10. Rates should be quoted clearly both in figures and words.

11. Lumpsum estimates at per cent below or above sanctioned amount will not be accepted.

Abstract estimate for repairing the sluice and channels of Thonnur Motikere Tank, Seringapatam Taluk.

No.	Items of work	Unit	Quantity	Rate	
				In figures	In words
	1. *Improving the existing sluice.*			Rs.	Rs.
1	Removing boulders and portion of old masonry ...	Lump	sum Rs.		
2	Excavating foundation in rocky soil ...	C.yd.	7		
3	Size stone in mortar	C.ft.	1,670		
4	Burnt stone slabs 9" thick	S.ft.	20		
5	Burnt stone slabs 6" thick	"	79		
6	Surki mortar plastering	Lump	sum Rs.		
7	Cutting grooves	R.ft.	16		
8	Sluice with shutter arrangements screw gearing plug and rod arrangements, etc., complete.	Lump	sum Rs.		
	2. *Repairs to left channel.*				
1	Repairs to the existing madavoys masonry work fixing C. I. pipes.	Each	8		
2	Supplying and fixing C. I. pipes ...	cw.	41.43/56		
3	Fixing burnt stone slabs below the C. I. pipes to prevent damage by the raiyats.	S.ft.	144		
4	Repairs to channel here and there ...	Lump	sum Rs.		
5	Providing and fixing mile stone including cutting figure and painting.	Each	1		
6	Providing and fixing furlong stones including cutting figures and painting, etc., complete.	"	7		

No.	Items of work	Unit	Quantity	Rate	
				In figures	In words
	3. *Repairs to the right channel.*			Rs.	Rs.
1	Constructing masonry C. I pipe madavoys in place of open cuts masonry work only.	Each	10		
2	Supplying and fixing C. I. pipes 12' long	cw.	30 75/112		
3	Repairs to channel here and there details to be furnished during execution.	Lump	sum Rs.		
4	Providing and fixing mile stone including cutting figures and painting, etc.	Each	1		
5	Providing and fixing furlong stones including cutting figures and painting, etc.	"	7		
	4. *Repairs to the dividing cisterns.*				
1	Repairing the dividing cistern by constructing the vents in cut stone and fixing with locking arrangements.	Lump	sum Rs.		

K. NARAYANA IYENGAR,
Executive Engineer.

SPECIAL DIVISION.

Notice dated 2nd July 1931.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Special Division, Mysore, up to 25th July 1931, till 12 noon for constructing a First Floor to the Ayurvedic and Unani College at Mysore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1932.

2. The detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore, between the hours of 11 A.M. and 5 P.M. on the working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees five hundred only (Rs. 500) in cash as earnest money, and be superscribed "Tender for constructing a First Floor to the Ayurvedic and Unani College at Mysore," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer of Mysore who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

No tender stating "percentage less than the lowest tender or as per estimated rates" will be accepted.

10. Once the tender has been accepted no claim for any concessions or higher rates will be entertained.

11. The work should be executed as per specification to be given by the Executive Engineer, Special Division.

12. The decision of the Chief Engineer in all matters regarding measurements, rates, etc., shall be final and legally binding.

13. The rates tendered should include all incidental charges for water, electric power, scaffolding, etc.